



Ref. 90-1222-02.11070

January 9, 2006

Mr. Robert Stone
Humboldt County Department of Health and Human Services
Division of Environmental Health
100 H Street, Suite 100
Eureka, CA 95501

Re: Quarterly Monitoring Data for September 2005
Nilsen Company, 424 Main Street, Ferndale, California
LOP #12070

Dear Mr. Stone:

On behalf of the Nilsen Company, Winzler & Kelly Consulting Engineers (Winzler & Kelly) is submitting the following quarterly monitoring data collected in September 2005 for the above-referenced site. The purpose of this letter report is to document the activities, results, and findings of the quarterly monitoring program. All figures referred to herein are included in Appendix A. All tables and charts are included in Appendix B, laboratory analytical reports are contained in Appendix C, Winzler & Kelly's Standard Operating Procedures (SOP) are contained in Appendix D, and field notes are contained in Appendix E.

Quarterly Monitoring Activities

On September 22, 2005 a Winzler & Kelly technician obtained water levels from monitoring wells MW-1, MW-2, MW-3, MW-5, MW-6, MW-8, MW-9 and MW-10 in order to calculate groundwater gradient. The site monitoring wells were then purged and sampled according to Winzler & Kelly's SOP for "*Monitoring Well Purging and Sampling Activities*" found in Appendix D. During purging, pH, temperature, dissolved oxygen, and specific conductivity readings were also measured. A regional map, site vicinity map, and site map with groundwater gradient and well locations are shown on Figures 1, 2, and 3 respectively (Appendix A).

Hydrographic Data

Depth to water measurements were collected after removing all well caps and allowing the wells to equalize for at least 15 minutes in accordance with Winzler & Kelly's SOP for "*Groundwater Level Measurements and Free Phase Hydrocarbon Measurements*" (Appendix D). Depth to water from the top of the well casing was measured for each well and results are included in Table 3, Appendix B.

Mr. Robert Stone
January 9, 2006
Page 2

The calculated groundwater gradient using wells MW-1, MW-5, MW-6, MW-8, MW-9, and MW-10 was calculated to be 91.04° Azimuth at a magnitude of 1.06 feet per 100 feet (Table 3, Appendix B). Groundwater gradient calculated from data collected at MW-1, MW-5, MW-6, and MW-10 should be more closely representative of groundwater conditions nearest to the former UST. The calculated groundwater gradient using monitoring wells MW-1, MW-5, MW-6 and MW-10 for the September 2005 sampling event was similar to previously calculated groundwater gradients for this site with the calculated gradient being 86.34° Azimuth with a magnitude of 1.16 feet per 100 feet. Table 4 in Appendix B shows the historical groundwater gradient summary calculated using these wells and Figure 3 in Appendix A shows the groundwater gradient calculated for the September 2005 sampling event, using these monitoring wells.

Depth to water data for the September 2005 sampling event were submitted electronically to the State Water Resources Control Board Geotracker System on October 17, 2005.

Dissolved Oxygen Measurements

Field measurements of dissolved oxygen (DO) concentrations were performed during this quarterly monitoring event using a Hach titration kit due to the unavailability of the field meter. The historical DO readings are displayed in Table 5, Appendix B.

Water Sampling

On September 22-23, 2005, monitoring wells MW-1, MW-2, MW-3, MW-5, MW-6, MW-8, MW-9 and MW-10 were purged in accordance with Winzler & Kelly's Standard Operating Procedure for "*Monitoring Well Purging and Sampling Activities*" (Appendix D). As standard procedure, measurements of temperature, conductivity, and pH of purge water from each well are made to verify that equilibrium has been attained prior to sampling. After purging at least three wetted casing volumes of water from each monitoring well, the water level was allowed to recover to approximately 80% of its pre-purge level before sampling. Groundwater monitoring wells were sampled on September 23, 2005, within 24 hours of purging.

During purging and sampling, petroleum odor was noted at well MW-6, and petroleum odor and sheen was noted at monitoring well MW-1. Petroleum odor and sheen were not detected in any of the remaining monitoring wells.

Mr. Robert Stone
January 9, 2006
Page 3

As part of the quarterly groundwater monitoring program, groundwater samples collected from site monitoring wells MW-2, MW-3, MW-5, MW-9 and MW-10 were analyzed for the following:

- Total Petroleum Hydrocarbons as Gasoline (TPH-G) by EPA Method 5030/GCFID/8015B, and
- Benzene, Toluene, Ethylbenzene, and Xylenes, including m,p-Xylene and o-Xylene (BTEX) and Methyl Tertiary Butyl Ether (MTBE) by EPA Method 5030/8021B.

Monitoring wells MW-1, MW-6, and MW-8 were analyzed for the following:

- TPH-G by EPA Method 8260B,
- BTEX, and the five fuel oxygenates, MTBE, Di-isopropyl Ether (DIPE), Ethyl Tertiary Butyl Ether (ETBE), Tertiary Amyl Methyl Ether (TAME), Tertiary Butyl Alcohol (TBA), by EPA Method 8260B.

Groundwater Analytical Results

The sample collected from monitoring well MW-1 contained concentrations of TPH-G, Benzene, Toluene, Ethylbenzene, and Xylenes above the laboratory detection limits. The five fuel oxygenates were below the laboratory detection limits. The September 2005 sampling event reported a TPH-G level at 9,300 parts per billion (ppb). This result is lower than the June 2005 result for TPH-G, and lower than the average of previous readings and is consistent with a decreasing trend as shown on Chart 1, Appendix B. Benzene, Toluene, Ethylbenzene and Xylene levels also show a decreasing trend with concentrations of 31 ppb, 3.5 ppb, 25 ppb and 7.62 ppb, respectively (Table 1, Appendix B).

All constituents tested for in wells MW-2, MW-3 and MW-5 were reported concentrations below the laboratory detection limits.

The sample collected from MW-6 reported TPH-G and MTBE concentrations at 62 ppb and 20 ppb, respectively. Both TPH-G and MTBE concentrations are lower than the previous monitoring event and are continuing the decreasing trend. All other constituents were below the laboratory detection limits. TPH-G results have decreased slightly in this well as shown on Chart 3, Appendix B.

Monitoring wells MW-8, MW-9 and MW-10 were tested for a third time since being installed on February 24, 2005. MW-8 reported MTBE at 14 ppb, which is similar to the March and June 2005 reported concentrations of 10 ppb and 11 ppb, respectively. All other constituents were below laboratory detection limits for this monitoring event.

Mr. Robert Stone
January 9, 2006
Page 4

Monitoring wells MW-9 and MW-10 did not report any constituent above laboratory detection limits for this September 2005 monitoring event. This is consistent with the June 2005 monitoring event.

Laboratory analytical results for the September 2005 sampling event were submitted electronically to the State Water Resources Control Board Geotracker System on October 17, 2005.

Disposition of Wastewater

Two 55-gallon drums of purge water are stored at the site. One of the drums holds purge water generated during groundwater sampling of the contaminated wells MW-1, MW-6, and MW-8. The other drum is storing purge water from the sampling of wells MW-2, MW3, MW-5, MW-9, and MW-10. When full, the drum containing purged water from the contaminated wells will be disposed of at the City of Eureka's wastewater treatment plant. Arrangements for this disposal will be made when necessary. The drum containing purge water from wells MW-2, MW3, MW-5, MW-9, and MW-10 will be spray irrigated at the site in a manner that will avoid runoff or ponding.

Quality Assurance/Quality Control (QA/QC)

A trip blank was submitted with the groundwater samples, but was not analyzed since at least one of the groundwater samples was below the detection limits for all analytes tested. Laboratory QA/QC was provided by the use of lab Method Blanks to preclude false positive analysis of analytes and the use of Laboratory Control Spike samples (LCS) to evaluate the percentage recovery of target analytes during analysis. Toluene, Ethylbenzene and Xylenes were detected below quantitation limits in the Method Blank.

The lab also noted:

Gasoline Components/Additives:

- The reporting limit for MTBE was raised for sample MW-1 due to matrix interference.
- Sample MW-6 does not present a peak pattern consistent with that of gasoline. The reported result represents the amount of material in the gasoline range.
- The gasoline value for sample MW-1 includes the reported gasoline components in addition to other peaks in the gasoline range.
- The relative percent difference (RPD) for the laboratory control samples was above the upper acceptance limit for TBA. This indicates that the results could be variable. Since there were no detectable levels of the analyte in the samples, the data were accepted.

Mr. Robert Stone
January 9, 2006
Page 5

Conclusions & Recommendations

- The groundwater gradient on September 22, 2005, calculated at 1.06 feet per 100 feet and flowed at 91.04° Azimuth, is within the range of previous calculations.
- Groundwater contaminant levels continue to show a declining trend.
- Groundwater from MW-1 had concentrations of TPH-G, Benzene, Toluene, Ethylbenzene, and Xylenes above laboratory detection limits, but lower than the previous monitoring event.
- MW-6 reported concentrations of TPH-G and MTBE above laboratory detection limits, but lower than the previous sampling event.
- MW-8 reported concentrations of MTBE, which were similar to that of the two previous sampling events.
- The next quarterly monitoring event is scheduled for December 2005.


If you have any questions or comments, please do not hesitate to call.


Sincerely,
WINZLER & KELLY

Prepared by:


Gary S. Lester
Staff Scientist

Reviewed by:


Patrick Kaspari, PE #CO55722
Project Engineer



gl

Enclosures: Appendix A: Figures
 Figure 1 Regional Map
 Figure 2 Vicinity Map
 Figure 3 Groundwater Gradient

Appendix B: Tables
 Table 1 Quarterly Groundwater Monitoring Results
 Table 2 Groundwater Measurements
 Table 3 Groundwater Gradient Summary
 (MW-1, MW-5, MW-6, MW-8, MW-9, MW-10)
 Table 4 Groundwater Gradient Summary
 (MW-1, MW-5, MW-6, MW-10)
 Table 5 Dissolved Oxygen Measurements
 Chart 1 MW-1, TPH-G Concentrations and Groundwater Elevations
 Chart 2 MW-6, TPH-G Concentrations and Groundwater Elevations



Mr. Robert Stone

January 9, 2006

Page 6

- Appendix C: Laboratory Analytical Reports
- Appendix D: Winzler & Kelly's Standard Operating Procedures
- Appendix E: Field Notes

c: Mr. Dennis Nilsen, Nilsen Company, 502 Broadway, Eureka, CA 95501

Appendix A

Figures





FIGURE 1



WINZLER & KELLY



VICINITY MAP

Scale: 1" = 2000'

FIGURE 2

WASHINGTON

MW-3
(43.91)

SS

(E) 6" SS

4" WATER MAIN

SCALE: 1" = 50'
SEE NOTE 2

NOTE:

- The location of sanitary sewer and water main utility lines are from Oscar Larson & Associates drawings and based on field observations only. Exact routing of piping is unknown.
- Property lines and utilities are not a product of survey.

LEGEND:



MONITORING WELLS INSTALLED
JULY, 1992 (M-1, M-2, M-3)



MONITORING WELLS INSTALLED
JULY, 1995 (M-4 AND M-5)



MONITORING WELLS INSTALLED
OCTOBER 1998 (M-6 & M-7)



MONITORING WELLS INSTALLED
FEBRUARY 2005 (MW-8, MW-9, MW-10)

PL

PROPERTY LINE - SEE NOTE 2

(E) 6"

SS

EXISTING SANITARY SEWER
(SEE NOTES 1 AND 2)




EXISTING WATER MAIN
(SEE NOTES 1 AND 2)

(49.82)

GROUNDWATER ELEVATION

GROUNDWATER FLOW
DIRECTION = 91.04 AZ.
1.06 FT./100 FT.
SEPTEMBER 2005

BERDING



GROUNDWATER GRADIENT
NILSEN COMPANY, FERNDALE

FIGURE 3



WINZLER & KELLY

Appendix B

Tables and Charts

TABLE 1
QUARTERLY GROUNDWATER MONITORING RESULTS
Nilsen Co. Ferndale LOP #12070
All results reported in parts per billion (ppb)

| Sample ID | Sample Date | TPH-G | Benzene | Toluene | Ethyl benzene | Xylenes | MTBE | Ethanol | Methanol | TBA | DIPE | ETBE | TAME |
|-----------|-------------|--------|---------|---------|---------------|---------|------|---------|----------|------|-------|-------|------|
| MW-1 | 27-May-93 | 17,000 | 380 | 130 | 500 | 590 | NT | NT | NT | NT | NT | NT | NT |
| | 3-Jan-94 | 14,000 | 360 | 86 | 190 | 190 | NT | NT | NT | NT | NT | NT | NT |
| | 24-Feb-94 | 15,000 | 470 | 99 | 330 | 330 | NT | NT | NT | NT | NT | NT | NT |
| | 8-Jun-94 | 17,000 | 500 | 100 | 340 | 340 | NT | NT | NT | NT | NT | NT | NT |
| | 18-Aug-94 | 14,000 | 290 | 84 | 230 | 230 | NT | NT | NT | NT | NT | NT | NT |
| | 15-Nov-94 | 14,000 | 450 | 91 | 250 | 250 | NT | NT | NT | NT | NT | NT | NT |
| | 22-Feb-95 | 16,000 | 420 | 86 | 300 | 290 | NT | NT | NT | NT | NT | NT | NT |
| | 26-Jun-95 | 14,000 | 390 | 30 | 180 | 220 | NT | NT | NT | NT | NT | NT | NT |
| | 26-Sep-95 | 15,000 | 400 | 78 | 280 | 270 | NT | NT | NT | NT | NT | NT | NT |
| | 24-Jan-96 | 14,000 | 310 | 38 | 250 | 220 | NT | NT | NT | NT | NT | NT | NT |
| | 29-Apr-96 | 19,000 | 300 | 36 | 250 | 240 | NT | NT | NT | NT | NT | NT | NT |
| | 18-Jul-96 | 14,000 | 360 | 80 | 230 | 230 | NT | NT | NT | NT | NT | NT | NT |
| | 23-Oct-96 | 15,000 | 230 | 18 | 140 | 150 | NT | NT | NT | NT | NT | NT | NT |
| | 9-Apr-97 | 14,000 | 230 | 22 | 190 | 180 | <85 | NT | NT | NT | NT | NT | NT |
| | 24-Jul-97 | 12,000 | 200 | 13 | 120 | 120 | <85 | NT | NT | NT | NT | NT | NT |
| | 21-Oct-97 | 14,000 | 290 | 18 | 180 | 190 | <85 | NT | NT | NT | NT | NT | NT |
| | 13-Jan-98 | 12,000 | 360 | 25 | 190 | 160 | <90 | NT | NT | NT | NT | NT | NT |
| | 15-Oct-98 | 17,000 | 110 | 290 | 50 | 110 | NT | NT | NT | NT | NT | NT | NT |
| | 25-Feb-99 | 15,000 | 440 | 24 | 200 | 150 | NT | NT | NT | NT | NT | NT | NT |
| | 1-Jul-03 | 17,000 | 380 | <220 | 84 | 40 | <160 | NT | NT | NT | NT | NT | NT |
| | 26-Sep-03 | 5,300 | 140 | 4.0 | 16 | 2.6 | 1.3 | <5.0 | <50 | <20 | <2.0 | <2.0 | <2.0 |
| | 24-Dec-03 | 12,000 | 170 | 12 | 68 | 28.3 | <1.0 | <500 | <500 | <20 | <1.0 | <1.0 | <1.0 |
| | 5-Mar-04 | 5,100 | 180 | 14 | 60 | 25.7 | <1.0 | NT | NT | <10 | <1.0 | <1.0 | <1.0 |
| | 14-Jul-04 | 11,000 | 140 | 13 | 54 | 23.7 | <8.0 | NT | NT | <10 | <1.0 | <1.0 | <1.0 |
| | 26-Oct-04 | 11,000 | 53 | 8.6 | 45 | 20.3 | <5.0 | <500 | <500 | <10 | <1.0 | <1.0 | <1.0 |
| | 7-Dec-04 | 12,000 | 53 | 8.3 | 48 | 22.4 | <6.0 | <500 | <500 | <10 | <1.0 | <1.0 | <1.0 |
| | 03-Mar-05 | 7,100 | 58 | <60 | 34 | 11 | <60 | NT | NT | NT | NT | NT | NT |
| | 28-Jun-05 | 9,400 | 35 | 4.1 | 28 | 10.7 | <8.0 | <500 | <500 | <10 | <1.0 | <1.0 | <1.0 |
| | 23-Sep-05 | 9,300 | 31 | 3.5 | 25 | 7.62 | <15 | NT | NT | <10 | <1.0 | <1.0 | <1.0 |
| MW-2 | 27-May-93 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 3-Jan-94 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 24-Feb-94 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 8-Jun-94 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 18-Aug-94 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 1-Jul-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 26-Sep-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 24-Dec-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 5-Mar-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 14-Jul-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 26-Oct-04 | <50 | <0.50 | <0.50 | <0.50 | 0.54 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 6-Dec-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 03-Mar-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 28-Jun-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 23-Sep-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| MW-3 | 27-May-93 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 3-Jan-94 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 24-Feb-94 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 8-Jun-94 | <50 | <0.30 | <0.30 | <0.50 | 1.7* | NT | NT | NT | NT | NT | NT | NT |
| | 18-Aug-94 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 1-Jul-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 26-Sep-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 24-Dec-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 5-Mar-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 14-Jul-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 26-Oct-04 | <50 | <0.50 | 1.2 | 0.71 | 2.64 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 6-Dec-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| MW-4 | 03-Mar-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 28-Jun-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 23-Sep-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 3-Aug-95 | 60 | 1.1 | <0.30 | <0.50 | 0.72 | NT | NT | NT | NT | NT | NT | NT |
| | 26-Sep-95 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 24-Jan-96 | 240 | 1.1 | <0.30 | 0.56 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 29-Apr-96 | 330 | 1.8 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 18-Jul-96 | 100 | 0.37 | <0.30 | <0.50 | <0.50 | NT | NT | NT | NT | NT | NT | NT |
| | 23-Oct-96 | 210 | 0.72 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 9-Apr-97 | 150 | 0.34 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 24-Jul-97 | 55 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 21-Oct-97 | 220 | 0.78 | <0.30 | 0.58 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 13-Jan-98 | 420 | 1.9 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 15-Oct-98 | 860 | 6.80 | 1.2 | 2.1 | 0.86 | NT | NT | NT | NT | NT | NT | NT |
| | 25-Feb-99 | 310 | 0.56 | <0.30 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT | NT |
| | 1-Jul-03 | 190 | <0.50 | <1.2 | <1.0 | <2.6 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 26-Sep-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <2.0 | <5.0 | <5.0 | <5.0 | <0.50 | <0.50 | <1.0 |
| | 24-Dec-03 | 58 | <0.50 | <0.50 | <0.50 | <1.0 | <1.0 | <500 | <500 | <20 | <1.0 | <1.0 | <1.0 |
| | 4-Mar-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <1.0 | NT | NT | <10 | <1.0 | <1.0 | <1.0 |
| | 14-Jul-04 | 170 | <0.50 | <0.50 | <0.50 | <1.0 | <1.0 | NT | NT | <10 | <1.0 | <1.0 | <1.0 |

Monitoring Well 4 abandoned

TABLE 1
QUARTERLY GROUNDWATER MONITORING RESULTS
Nilsen Co. Ferndale LOP #12070
All results reported in parts per billion (ppb)

| Sample ID | Sample Date | TPH-G | Benzene | Toluene | Ethyl benzene | Xylenes | MTBE | Ethanol | Methanol | TBA | DIPE | ETBE | TAME |
|-----------|-----------------------------|-------|---------|---------|---------------|---------|-------|---------|----------|------|------|------|------|
| MW-5 | 3-Aug-95 | <50 | <0.30 | <0.30 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT | NT |
| | 26-Sep-95 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 24-Jan-96 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 29-Apr-96 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 18-Jul-96 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 23-Oct-96 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 9-Apr-97 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 24-Jul-97 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 21-Oct-97 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 13-Jan-98 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 15-Oct-98 | <50 | <0.30 | <0.30 | <0.50 | <0.50 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 1-Jul-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 26-Sep-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 24-Dec-03 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 4-Mar-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <1.0 | NT | NT | NT | NT | NT | NT |
| | 14-Jul-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 26-Oct-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 7-Dec-04 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 03-Mar-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 28-Jun-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 23-Sep-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| MW-6 | 14-Oct-98 | 210 | 7.1 | 2.7 | <0.50 | 2.2 | NT | NT | NT | NT | NT | NT | NT |
| | 25-Feb-99 | 140 | 5.1 | <1.2 | <1.5 | 1.7 | NT | NT | NT | NT | NT | NT | NT |
| | 1-Jul-03 | 130 | <1.1 | <1.8 | <0.50 | <1.0 | 100 | NT | NT | NT | NT | NT | NT |
| | 26-Sep-03 | 77 | <0.50 | <0.50 | <0.50 | <1.0 | 68 | <5.0 | <50 | <5.0 | <1.0 | <1.0 | 2.6 |
| | 24-Dec-03 | 200 | <0.50 | <0.50 | <0.50 | <1.0 | 110 | <500 | <500 | <20 | <1.0 | <1.0 | 4.1 |
| | 4-Mar-04 | 140 | <0.50 | <0.50 | <0.50 | <1.0 | 110 | NT | NT | <10 | <1.0 | <1.0 | 3.1 |
| | 14-Jul-04 | 99 | <0.50 | <0.50 | <0.50 | <1.0 | 67 | NT | NT | <10 | <1.0 | <1.0 | 3.0 |
| | 26-Oct-04 | 160 | 0.57 | <0.50 | <0.50 | <1.0 | 54 | <500 | <500 | <10 | <1.0 | <1.0 | 2.3 |
| | 7-Dec-04 | 160 | 0.57 | <0.50 | <0.50 | <1.0 | 62 | <500 | <500 | <10 | <1.0 | <1.0 | 2.4 |
| | 03-Mar-05 | 86 | <0.50 | <0.50 | <0.50 | <1.0 | 49 | NT | NT | NT | NT | NT | NT |
| MW-7 | 28-Jun-05 | 89 | <0.50 | <0.50 | <0.50 | <1.0 | 53 | <500 | <500 | <10 | <1.0 | <1.0 | 2.1 |
| | 23-Sep-05 | 62 | <0.50 | <0.50 | <0.50 | <1.0 | 20 | NT | NT | <10 | <1.0 | <1.0 | <1.0 |
| | 14-Oct-98 | 3,000 | 7.1 | 2.7 | 17 | 3.4 | NT | NT | NT | NT | NT | NT | NT |
| | 25-Feb-99 | 3,200 | 5.6 | 2.8 | 19 | 150 | NT | NT | NT | NT | NT | NT | NT |
| MW-8 | 1-Jul-03 | 1,400 | 11 | <13 | 4.2 | 1.0 | <32 | NT | NT | NT | NT | NT | NT |
| | 26-Sep-03 | 280 | 1.2 | 0.67 | 0.74 | <1.0 | <0.50 | <5.0 | <50 | <5.0 | <1.0 | <1.0 | <1.0 |
| | Monitoring Well 7 abandoned | | | | | | | | | | | | |
| MW-8 | 3-Mar-05 | 78 | 0.83 | <0.50 | <0.50 | <1.0 | 10 | NT | NT | NT | NT | NT | NT |
| | 28-Jun-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | 11 | <500 | <500 | <10 | <1.0 | <1.0 | <1.0 |
| | 23-Sep-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | 14 | NT | NT | <10 | <1.0 | <1.0 | <1.0 |
| MW-9 | 3-Mar-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 28-Jun-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 23-Sep-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| MW-10 | 3-Mar-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 28-Jun-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |
| | 23-Sep-05 | <50 | <0.50 | <0.50 | <0.50 | <1.0 | <3.0 | NT | NT | NT | NT | NT | NT |

TABLE 2
GROUNDWATER MEASUREMENTS
Nilsen, LOP #12070

| Well No. | Sample Date | TOC | DTW | GWE |
|--|-------------|-------|------|-------|
| MW-1 N = 2101294.7449 E = 5933038.33434 | 3-Aug-95 | 51.68 | 4.07 | 47.61 |
| | 24-Aug-95 | 51.68 | 3.95 | 47.73 |
| | 26-Sep-95 | 51.68 | 3.92 | 47.76 |
| | 18-Oct-95 | 51.68 | 4.18 | 47.50 |
| | 17-Nov-95 | 51.68 | 4.39 | 47.29 |
| | 24-Jan-96 | 51.68 | 2.77 | 48.91 |
| | 15-Feb-96 | 51.68 | 4.71 | 46.97 |
| | 8-Mar-96 | 51.68 | 3.46 | 48.22 |
| | 29-Apr-96 | 51.68 | 3.40 | 48.28 |
| | 31-May-96 | 51.68 | 5.04 | 46.64 |
| | 17-Jun-96 | 51.68 | 4.43 | 47.25 |
| | 18-Jul-96 | 51.68 | 4.20 | 47.48 |
| | 26-Aug-96 | 51.68 | 5.46 | 46.22 |
| | 10-Sep-96 | 51.68 | 4.77 | 46.91 |
| | 23-Oct-96 | 51.68 | 4.09 | 47.59 |
| | 14-Nov-96 | 51.68 | 4.92 | 46.76 |
| | 24-Dec-96 | 51.68 | 3.28 | 48.40 |
| | 9-Apr-97 | 51.68 | 3.50 | 48.18 |
| | 24-Jul-97 | 51.68 | 6.45 | 45.23 |
| | 21-Oct-97 | 51.68 | 5.15 | 46.53 |
| | 13-Jan-98 | 51.68 | 3.87 | 47.81 |
| | 30-Jun-02 | 51.68 | 5.53 | 46.15 |
| | 26-Sep-03 | 51.68 | 4.95 | 46.73 |
| | 22-Dec-03 | 51.68 | 3.55 | 48.13 |
| | 4-Mar-04 | 51.68 | 3.82 | 47.86 |
| | 13-Jul-04 | 51.68 | 4.94 | 46.74 |
| | 26-Oct-04 | 51.68 | 3.25 | 48.43 |
| | 6-Dec-04 | 51.68 | 3.14 | 48.54 |
| | 3-Mar-05 | 53.03 | 3.21 | 49.82 |
| | 28-Jun-05 | 53.03 | 3.61 | 49.42 |
| | 22-Sep-05 | 53.03 | 4.07 | 48.96 |
| MW-2 N = 2101203.89767 E = 5933252.62818 | 18-Jul-96 | 47.87 | 3.19 | 44.68 |
| | 26-Aug-96 | 47.87 | 3.34 | 44.53 |
| | 10-Sep-96 | 47.87 | 3.41 | 44.46 |
| | 23-Oct-96 | 47.87 | 3.67 | 44.20 |
| | 14-Nov-96 | 47.87 | 3.68 | 44.19 |
| | 24-Dec-96 | 47.87 | 1.97 | 45.90 |
| | 9-Apr-97 | 47.87 | 3.23 | 44.64 |
| | 24-Jul-97 | 47.87 | 4.46 | 43.41 |
| | 21-Oct-97 | 47.87 | 3.55 | 44.32 |
| | 13-Jan-98 | 47.87 | 1.79 | 46.08 |
| | 30-Jun-02 | 47.87 | 3.51 | 44.36 |
| | 26-Sep-03 | 47.87 | 2.80 | 45.07 |
| | 22-Dec-03 | 47.87 | 2.99 | 44.88 |
| | 4-Mar-04 | 47.87 | 3.29 | 44.58 |
| | 13-Jul-04 | 47.87 | 3.71 | 44.16 |
| | 26-Oct-04 | 47.87 | 3.15 | 44.72 |
| | 6-Dec-04 | 47.87 | 3.32 | 44.55 |
| | 3-Mar-05 | 49.23 | 3.11 | 46.12 |
| | 28-Jun-05 | 49.23 | 3.36 | 45.87 |
| | 22-Sep-05 | 49.23 | 3.74 | 45.49 |

TABLE 2
GROUNDWATER MEASUREMENTS
Nilsen, LOP #12070

| Well No. | Sample Date | TOC | DTW | GWE |
|--------------------------------------|-------------|-------|------|-------|
| MW-3 N = 10402.72 E = 20689.67 | 18-Jul-96 | 48.47 | 4.17 | 44.30 |
| | 26-Aug-96 | 48.47 | 4.37 | 44.10 |
| | 10-Sep-96 | 48.47 | 4.97 | 43.50 |
| | 23-Oct-96 | 48.47 | 4.66 | 43.81 |
| | 14-Nov-96 | 48.47 | 4.59 | 43.88 |
| | 24-Dec-96 | 48.47 | 4.17 | 44.30 |
| | 9-Apr-97 | 48.47 | 4.24 | 44.23 |
| | 24-Jul-97 | 48.47 | 5.45 | 43.02 |
| | 21-Oct-97 | 48.47 | 4.41 | 44.06 |
| | 13-Jan-98 | 48.47 | 3.83 | 44.64 |
| | 30-Jun-02 | 48.47 | 4.54 | 43.93 |
| | 26-Sep-03 | 48.47 | 5.33 | 43.14 |
| | 22-Dec-03 | 48.47 | 4.27 | 44.20 |
| | 4-Mar-04 | 48.47 | 4.70 | 43.77 |
| | 13-Jul-04 | 48.47 | 4.32 | 44.15 |
| | 26-Oct-04 | 48.47 | 5.41 | 43.06 |
| | 6-Dec-04 | 48.47 | 5.48 | 42.99 |
| | 28-Jun-05 | 48.47 | 4.26 | 44.21 |
| | 22-Sep-05 | 48.47 | 4.56 | 43.91 |
| MW-4 | 3-Aug-95 | 51.28 | 3.89 | 47.39 |
| | 24-Aug-95 | 51.28 | 4.07 | 47.21 |
| | 26-Sep-95 | 51.28 | 4.49 | 46.79 |
| | 18-Oct-95 | 51.28 | 4.07 | 47.21 |
| | 17-Nov-95 | 51.28 | 4.62 | 46.66 |
| | 24-Jan-96 | 51.28 | 2.06 | 49.22 |
| | 15-Feb-96 | 51.28 | 3.37 | 47.91 |
| | 8-Mar-96 | 51.28 | 2.95 | 48.33 |
| | 29-Apr-96 | 51.28 | 3.17 | 48.11 |
| | 31-May-96 | 51.28 | 3.76 | 47.52 |
| | 17-Jun-96 | 51.28 | 3.88 | 47.40 |
| | 18-Jul-96 | 51.28 | 4.17 | 47.11 |
| | 26-Aug-96 | 51.28 | 4.63 | 46.65 |
| | 10-Sep-96 | 51.28 | 4.95 | 46.33 |
| | 23-Oct-96 | 51.28 | 3.97 | 47.31 |
| | 14-Nov-96 | 51.28 | 3.82 | 47.46 |
| | 24-Dec-96 | 51.28 | 2.66 | 48.62 |
| | 9-Apr-97 | 51.28 | 3.61 | 47.67 |
| | 24-Jul-97 | 51.28 | 5.50 | 45.78 |
| | 21-Oct-97 | 51.28 | 3.81 | 47.47 |
| | 13-Jan-98 | 51.28 | 2.19 | 49.09 |
| | 30-Jun-02 | 51.28 | 3.35 | 47.93 |
| | 26-Sep-03 | 51.28 | 4.25 | 47.03 |
| | 22-Dec-03 | 51.28 | 2.95 | 48.33 |
| | 4-Mar-04 | 51.28 | 3.03 | 48.25 |
| | 13-Jul-04 | 51.28 | 3.75 | 47.53 |
| Monitoring Well 4 abandoned | | | | |

TABLE 2
GROUNDWATER MEASUREMENTS
Nilsen, LOP #12070

| Well No. | Sample Date | TOC | DTW | GWE |
|---|-----------------------------|-------|------|-------|
| MW-5 N = 2101306.27261 E = 5933070.12554 | 3-Aug-95 | 52.27 | 4.97 | 47.30 |
| | 24-Aug-95 | 52.27 | 5.02 | 47.25 |
| | 26-Sep-95 | 52.27 | 5.13 | 47.14 |
| | 18-Oct-95 | 52.27 | 4.92 | 47.35 |
| | 17-Nov-95 | 52.27 | 5.19 | 47.08 |
| | 24-Jan-96 | 52.27 | 2.73 | 49.54 |
| | 15-Feb-96 | 52.27 | 4.57 | 47.70 |
| | 8-Mar-96 | 52.27 | 2.87 | 49.40 |
| | 29-Apr-96 | 52.27 | 4.08 | 48.19 |
| | 31-May-96 | 52.27 | 4.76 | 47.51 |
| | 17-Jun-96 | 52.27 | 4.81 | 47.46 |
| | 18-Jul-96 | 52.27 | 5.10 | 47.17 |
| | 26-Aug-96 | 52.27 | 5.50 | 46.77 |
| | 10-Sep-96 | 52.27 | 5.61 | 46.66 |
| | 23-Oct-96 | 52.27 | 4.80 | 47.47 |
| | 14-Nov-96 | 52.27 | 4.97 | 47.30 |
| | 24-Dec-96 | 52.27 | 3.68 | 48.59 |
| | 9-Apr-97 | 52.27 | 4.42 | 47.85 |
| | 24-Jul-97 | 52.27 | 6.44 | 45.83 |
| | 21-Oct-97 | 52.27 | 5.10 | 47.17 |
| | 13-Jan-98 | 52.27 | 3.31 | 48.96 |
| | 30-Jun-02 | 52.27 | 3.96 | 48.31 |
| | 26-Sep-03 | 52.27 | 5.11 | 47.16 |
| | 22-Dec-03 | 52.27 | 4.58 | 47.69 |
| | 4-Mar-04 | 52.27 | 4.22 | 48.05 |
| MW-6 N = 2101295.52491 E = 5933015.13194 | 13-Jul-04 | 52.27 | 4.46 | 47.81 |
| | 26-Oct-04 | 52.27 | 3.07 | 49.20 |
| | 6-Dec-04 | 52.27 | 2.71 | 49.56 |
| | 3-Mar-05 | 53.64 | 3.30 | 50.34 |
| | 28-Jun-05 | 53.64 | 4.30 | 49.34 |
| | 22-Sep-05 | 53.64 | 5.02 | 48.62 |
| | 30-Jun-02 | 52.40 | 4.51 | 47.89 |
| | 26-Sep-03 | 52.40 | 4.54 | 47.86 |
| | 22-Dec-03 | 52.40 | 4.37 | 48.03 |
| | 4-Mar-04 | 52.40 | 4.41 | 47.99 |
| MW-7 | 13-Jul-04 | 52.40 | 4.49 | 47.91 |
| | 26-Oct-04 | 52.40 | 4.03 | 48.37 |
| | 6-Dec-04 | 52.40 | 3.97 | 48.43 |
| | 3-Mar-05 | 53.86 | 4.18 | 49.68 |
| | 28-Jun-05 | 53.86 | 4.38 | 49.48 |
| | 22-Sep-05 | 53.86 | 4.59 | 49.27 |
| | 30-Jun-02 | 50.44 | 3.34 | 47.10 |
| | 26-Sep-03 | 50.44 | 3.57 | 46.87 |
| | Monitoring Well 7 abandoned | | | |
| | | | | |
| MW-8 N = 2101278.10988 E = 5933045.49179 | 3-Mar-05 | 52.81 | 3.00 | 49.81 |
| | 28-Jun-05 | 52.81 | 3.49 | 49.32 |
| | 22-Sep-05 | 52.81 | 3.98 | 48.83 |
| MW-9 N = 2101254.31199 E = 5933042.47497 | 3-Mar-05 | 52.86 | 8.15 | 44.71 |
| | 28-Jun-05 | 52.86 | 3.21 | 49.65 |
| | 22-Sep-05 | 52.86 | 3.98 | 48.88 |
| MW-10 N = 2101214.18928 E = 5933122.15667 | 3-Mar-05 | 51.36 | 2.42 | 48.94 |
| | 28-Jun-05 | 51.36 | 2.85 | 48.51 |
| | 22-Sep-05 | 51.36 | 3.28 | 48.08 |

Top of Casing Elevation data for and subsequent to December 2004 event is based on Winzler and Kelly survey data.

Top of Casing Elevation data for and after March 2005 event is based on Ontiveros & Associates survey data performed on June 1, 2005.

Table 3
Groundwater Gradient Summary
Nilsen Company, LOP #12070

| Date | Gradient Direction (Degrees Azimuth) | Gradient Magnitude (feet/ 100 feet) |
|-----------|---|--|
| 25-Sep-03 | 92 | 1.40 |
| 22-Dec-03 | 90.04 | 1.45 |
| 04-Mar-04 | 101.01 | 1.49 |
| 13-Jul-04 | 99.39 | 1.47 |
| 26-Oct-04 | 83.86 | 1.85 |
| 06-Dec-04 | 85.80 | 1.97 |
| 28-Jun-05 | 82.63 | 1.73 |
| 22-Sep-05 | 91.04 | 1.06 |

Note:

September 2003 gradient calculated using monitoring wells MW-1 through MW-7.

From December 2003 to July 2004, gradient calculated using MW-1 through MW-6.

From October '04 until June '05, gradient calculated using monitoring wells MW-1, MW-2, MW-3, MW-5, and MW-6.

Sept 2005, gradient calculated using monitoring wells MW-1, MW-5, MW-6, MW-8, MW-9 and MW-10.

TABLE 4
GROUNDWATER GRADIENT SUMMARY
 Nilsen Company, LOP #12070

| Date | Gradient Direction (Degrees Azimuth) | Gradient Magnitude (feet/ 100 feet) |
|---|--------------------------------------|-------------------------------------|
| 03-Aug-95 | 79.70 | 0.94 |
| 24-Aug-95 | 99.97 | 1.66 |
| 26-Sep-95 | 117.48 | 2.77 |
| 18-Oct-95 | 125.92 | 0.81 |
| 18-Nov-95 | 138.73 | 1.80 |
| 24-Jan-96 | 246.10 | 1.87 |
| 15-Feb-96 | 288.52 | 2.81 |
| 08-Mar-96 | 222.91 | 3.89 |
| 29-Apr-96 | 125.06 | 0.48 |
| 31-May-96 | 276.52 | 2.91 |
| 17-Jun-96 | 259.98 | 0.63 |
| 18-Jul-96 | 104.80 | 1.13 |
| 26-Aug-96 | 264.02 | 1.69 |
| 10-Sep-96 | 131.97 | 1.63 |
| 23-Dec-96 | 132.14 | 0.79 |
| 14-Nov-96 | 288.84 | 2.09 |
| 24-Dec-96 | 283.30 | 0.68 |
| 09-Apr-97 | 116.94 | 1.48 |
| 24-Jul-97 | 271.62 | 1.93 |
| 21-Oct-97 | 294.68 | 2.72 |
| 13-Jan-98 | 281.32 | 4.03 |
| 01-Jul-03 | 266.47 | 6.71 |
| 25-Sep-03 | 258.96 | 1.29 |
| 22-Dec-03 | 21.45 | 1.93 |
| 04-Mar-04 | 308.03 | 1.10 |
| 13-Jul-04 | 261.42 | 3.25 |
| MW-4 was abandoned after the July 2004 monitoring event | | |
| 6-Dec-04 | 85.8 | 1.97 |
| 3-Mar-05 | 202.63 | 2.15 |
| 28-Jun-05 | 149.54 | 0.79 |
| 22-Sep-05 | 86.34 | 1.16 |
| Average | 193.04 | 1.99 |

Note:

- Gradient, from August 95 through July 2004,
calculated using data from wells MW-1, MW-4, and MW-5.
- Gradient, from December 2004
calculated using data from MW-1, MW-2, MW-3, MW-5, and MW-6
- Gradient, from March 2005
calculated using data from MW-1, MW-2, MW-3, MW-5, and MW-6
- Gradient, for September 2005
calculated using MW-1, MW-5, MW-6, and MW-10

TABLE 5
DISSOLVED OXYGEN MEASUREMENTS
Nilsen Company, LOP # 12070
(All results in mg/L)

| Date | MW-1 | MW-2 | MW-3 | MW-4 | MW-5 | MW-6 | MW-7 | MW-8 | MW-9 | MW-10 |
|-----------|--|------|------|------|------|------|------|------|------|-------|
| 25-Sep-03 | 1.4 | 2.8 | 2.1 | 0.6 | 4.9 | 0.9 | 7.4 | NA | NA | NA |
| 22-Dec-03 | 3.1 | 3.3 | 3.4 | 3.0 | 3.6 | 3.7 | NT | NA | NA | NA |
| 04-Mar-04 | 2.1 | 2.9 | 3.2 | 1.6 | 4.4 | 1.5 | NT | NA | NA | NA |
| 13-Jul-04 | 6.5 | 6.4 | 0.7 | 4.6 | 7.3 | 7.7 | NT | NA | NA | NA |
| 26-Oct-04 | 2.2 | 1.3 | 1.3 | NT | 1.5 | 2.1 | NT | NA | NA | NA |
| 06-Dec-04 | 0.6 | 0.8 | 0.5 | NT | 0.6 | 0.7 | NT | NA | NA | NA |
| 02-Mar-05 | 3.0 | 4.0 | 3.0 | NT | 5.0 | 0.8 | NT | NA | NA | NA |
| 28-Jun-05 | 0.6 | 1.4 | 6.0 | NT | 5.0 | 0.8 | NT | 0.4 | 1.0 | 3.0 |
| 23-Sep-05 | No measurements taken during this monitoring event | | | | | | | | | |

Chart 1
MW-1
TPH-G Concentration
&
Groundwater Elevation





Chart 2
MW-6
TPH-G Concentration
&
Groundwater Elevation



Appendix C

Laboratory Analytical Reports



October 06, 2005

Winzler and Kelly
633 Third Street
Eureka, CA 95501

Attn: Pat Kaspari

RE: 9012220211070, Nilsen Co., Ferndale

Order No.: 0509542
Invoice No.: 53340
PO No.:
ELAP No. 1247-Expires July 2006

SAMPLE IDENTIFICATION

| Fraction | Client Sample Description |
|----------|---------------------------|
| 01A | MW-5 |
| 02A | MW-10 |
| 03A | MW-2 |
| 04A | MW-3 |
| 05A | MW-8 |
| 06A | MW-6 |
| 07A | MW-1 |
| 08A | MW-9 |
| 08B | MW-9 |
| 08C | MW-9 |

ND = Not Detected at the Reporting Limit

Limit = Reporting Limit

All solid results are expressed on a wet-weight basis unless otherwise noted.

REPORT CERTIFIED BY

Laboratory Supervisor(s)

QA Unit

Jesse G. Chaney, Jr.
Laboratory Director

CLIENT: Winzler and Kelly
Project: 9012220211070, Nilsen Co., Ferndale
Lab Order: 0509542

CASE NARRATIVE**Gasoline Components/Additives:**

The reporting limit for MTBE was raised for sample MW-1 due to matrix interference.

Sample MW-6 does not present a peak pattern consistent with that of gasoline. The reported result represents the amount of material in the gasoline range.

The gasoline value for sample MW-1 includes the reported gasoline components in addition to other peaks in the gasoline range.

The relative percent difference (RPD) for the laboratory control samples was above the upper acceptance limit for TBA. This indicates that the results could be variable. Since there were no detectable levels of the analyte in the samples, the data were accepted.

Date: 06-Oct-05
WorkOrder: 0509542

ANALYTICAL REPORT

Client Sample ID: MW-5
Lab ID: 0509542-01A

Received: 9/23/05

Collected: 9/23/05 11:20

Test Name: BTEX

Reference: EPA 5030/EPA 8021B

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|-------------------------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| MTBE | ND | 3.0 | µg/L | 1.0 | | 10/4/05 |
| Benzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Toluene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Ethylbenzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| m,p-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| o-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Surrogate: Cis-1,2-Dichloroethylene | 98.0 | 85-115 | % Rec | 1.0 | | 10/4/05 |

Test Name: TPH as Gasoline

Reference: EPA 5030/GCFID(LUFT)/EPA 8015B

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|-------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| TPHC Gas (C6-C14) | ND | 50 | µg/L | 1.0 | | 10/4/05 |

Client Sample ID: MW-10

Received: 9/23/05

Collected: 9/23/05 11:25

Lab ID: 0509542-02A

Test Name: BTEX

Reference: EPA 5030/EPA 8021B

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|-------------------------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| MTBE | ND | 3.0 | µg/L | 1.0 | | 10/4/05 |
| Benzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Toluene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Ethylbenzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| m,p-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| o-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Surrogate: Cis-1,2-Dichloroethylene | 93.9 | 85-115 | % Rec | 1.0 | | 10/4/05 |

Test Name: TPH as Gasoline

Reference: EPA 5030/GCFID(LUFT)/EPA 8015B

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|-------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| TPHC Gas (C6-C14) | ND | 50 | µg/L | 1.0 | | 10/4/05 |

Date: 06-Oct-05
WorkOrder: 0509542

ANALYTICAL REPORT

Client Sample ID: MW-2
Lab ID: 0509542-03A

Received: 9/23/05

Collected: 9/23/05 11:39

Test Name: BTEX

Reference: EPA 5030/EPA 8021B

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|-------------------------------------|--------|--------|-------|-----|-----------|----------|
| MTBE | ND | 3.0 | µg/L | 1.0 | | 10/4/05 |
| Benzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Toluene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Ethylbenzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| m,p-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| o-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Surrogate: Cis-1,2-Dichloroethylene | 93.6 | 85-115 | % Rec | 1.0 | | 10/4/05 |

Test Name: TPH as Gasoline

Reference: EPA 5030/GCFID(LUFT)/EPA 8015B

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|-------------------|--------|-------|-------|-----|-----------|----------|
| TPHC Gas (C6-C14) | ND | 50 | µg/L | 1.0 | | 10/4/05 |

Client Sample ID: MW-3

Received: 9/23/05

Collected: 9/23/05 11:50

Lab ID: 0509542-04A

Test Name: BTEX

Reference: EPA 5030/EPA 8021B

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|-------------------------------------|--------|--------|-------|-----|-----------|----------|
| MTBE | ND | 3.0 | µg/L | 1.0 | | 10/4/05 |
| Benzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Toluene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Ethylbenzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| m,p-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| o-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Surrogate: Cis-1,2-Dichloroethylene | 86.5 | 85-115 | % Rec | 1.0 | | 10/4/05 |

Test Name: TPH as Gasoline

Reference: EPA 5030/GCFID(LUFT)/EPA 8015B

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|-------------------|--------|-------|-------|-----|-----------|----------|
| TPHC Gas (C6-C14) | ND | 50 | µg/L | 1.0 | | 10/4/05 |

Date: 06-Oct-05
WorkOrder: 0509542

ANALYTICAL REPORT

Client Sample ID: MW-8
Lab ID: 0509542-05A

Received: 9/23/05

Collected: 9/23/05 12:05

Test Name: Gasoline Components/Additives

Reference: LUFT/EPA 8260B Modified

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|-----------------------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| Methyl tert-butyl ether (MTBE) | 14 | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Tert-butyl alcohol (TBA) | ND | 10 | µg/L | 1.0 | | 10/3/05 |
| Di-isopropyl ether (DIPE) | ND | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Ethyl tert-butyl ether (ETBE) | ND | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Benzene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| Tert-amyl methyl ether (TAME) | ND | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Toluene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| Ethylbenzene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| m,p-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| o-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| Surrogate: 1,4-Dichlorobenzene-d4 | 97.9 | 80.8-139 | % Rec | 1.0 | | 10/3/05 |

Test Name: TPH as Gasoline

Reference: LUFT/EPA 8260B Modified

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| TPHC Gasoline | ND | 50 | µg/L | 1.0 | | 10/3/05 |

Client Sample ID: MW-6

Received: 9/23/05

Collected: 9/23/05 12:11

Lab ID: 0509542-06A

Test Name: Gasoline Components/Additives

Reference: LUFT/EPA 8260B Modified

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|-----------------------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| Methyl tert-butyl ether (MTBE) | 20 | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Tert-butyl alcohol (TBA) | ND | 10 | µg/L | 1.0 | | 10/3/05 |
| Di-isopropyl ether (DIPE) | ND | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Ethyl tert-butyl ether (ETBE) | ND | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Benzene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| Tert-amyl methyl ether (TAME) | ND | 1.0 | µg/L | 1.0 | | 10/3/05 |
| Toluene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| Ethylbenzene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| m,p-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| o-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/3/05 |
| Surrogate: 1,4-Dichlorobenzene-d4 | 92.4 | 80.8-139 | % Rec | 1.0 | | 10/3/05 |

Test Name: TPH as Gasoline

Reference: LUFT/EPA 8260B Modified

| <u>Parameter</u> | <u>Result</u> | <u>Limit</u> | <u>Units</u> | <u>DF</u> | <u>Extracted</u> | <u>Analyzed</u> |
|------------------|---------------|--------------|--------------|-----------|------------------|-----------------|
| TPHC Gasoline | 62 | 50 | µg/L | 1.0 | | 10/3/05 |

Date: 06-Oct-05
WorkOrder: 0509542

ANALYTICAL REPORT

Client Sample ID: MW-1
Lab ID: 0509542-07A

Received: 9/23/05

Collected: 9/23/05 12:22

Test Name: Gasoline Components/Additives

Reference: LUFT/EPA 8260B Modified

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|-----------------------------------|--------|----------|-------|-----|-----------|----------|
| Methyl tert-butyl ether (MTBE) | ND | 15 | µg/L | 1.0 | | 10/4/05 |
| Tert-butyl alcohol (TBA) | ND | 10 | µg/L | 1.0 | | 10/4/05 |
| Di-isopropyl ether (DIPE) | ND | 1.0 | µg/L | 1.0 | | 10/4/05 |
| Ethyl tert-butyl ether (ETBE) | ND | 1.0 | µg/L | 1.0 | | 10/4/05 |
| Benzene | 31 | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Tert-amyl methyl ether (TAME) | ND | 1.0 | µg/L | 1.0 | | 10/4/05 |
| Toluene | 3.5 | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Ethylbenzene | 25 | 0.50 | µg/L | 1.0 | | 10/4/05 |
| m,p-Xylene | 6.7 | 0.50 | µg/L | 1.0 | | 10/4/05 |
| o-Xylene | 0.92 | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Surrogate: 1,4-Dichlorobenzene-d4 | 86.3 | 80.8-139 | % Rec | 1.0 | | 10/4/05 |

Test Name: TPH as Gasoline

Reference: LUFT/EPA 8260B Modified

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|---------------|--------|-------|-------|----|-----------|----------|
| TPHC Gasoline | 9,300 | 2,500 | µg/L | 50 | | 10/4/05 |

Client Sample ID: MW-9

Received: 9/23/05

Collected: 9/23/05 12:30

Lab ID: 0509542-08A

Test Name: BTEX

Reference: EPA 5030/EPA 8021B

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|-------------------------------------|--------|--------|-------|-----|-----------|----------|
| MTBE | ND | 3.0 | µg/L | 1.0 | | 10/4/05 |
| Benzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Toluene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Ethylbenzene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| m,p-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| o-Xylene | ND | 0.50 | µg/L | 1.0 | | 10/4/05 |
| Surrogate: Cis-1,2-Dichloroethylene | 96.0 | 85-115 | % Rec | 1.0 | | 10/4/05 |

Test Name: TPH as Gasoline

Reference: EPA 5030/GCFID(LUFT)/EPA 8015B

| Parameter | Result | Limit | Units | DF | Extracted | Analyzed |
|-------------------|--------|-------|-------|-----|-----------|----------|
| TPHC Gas (C6-C14) | ND | 50 | µg/L | 1.0 | | 10/4/05 |

North Coast Laboratories, Ltd.

Date: 06-Oct-05

CLIENT: Winzler and Kelly
Work Order: 0509542
Project: 9012220211070, Nilsen Co., Ferndale

QC SUMMARY REPORT

Method Blank

| Sample ID: MB-100305 | Batch ID: R37259 | Test Code: 8260OXYW | Units: µg/L | Analysis Date: 10/3/05 8:28:00 AM | | | Prep Date: | | | | |
|--------------------------------|------------------|-------------------------|-------------|-----------------------------------|--------|----------|------------|-------------|------|----------|------|
| Client ID: | | Run ID: ORGCMS2_051003B | | SeqNo: | 536263 | | | | | | |
| Analyte | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| Methyl tert-butyl ether (MTBE) | ND | 1.0 | | | | | | | | | |
| Tert-butyl alcohol (TBA) | ND | 10 | | | | | | | | | |
| Di-isopropyl ether (DIPE) | ND | 1.0 | | | | | | | | | |
| Ethyl tert-butyl ether (ETBE) | ND | 1.0 | | | | | | | | | |
| Benzene | ND | 0.50 | | | | | | | | | |
| Tert-amyl methyl ether (TAME) | ND | 1.0 | | | | | | | | | |
| Toluene | ND | 0.50 | | | | | | | | | |
| Ethylbenzene | 0.07809 | 0.50 | | | | | | | | | |
| m,p-Xylene | ND | 0.50 | | | | | | | | | |
| o-Xylene | 0.1209 | 0.50 | | | | | | | | | |
| 1,4-Dichlorobenzene-d4 | 0.917 | 0.10 | 1.00 | 0 | 91.7% | 81 | 139 | 0 | | | J |
| Sample ID: MB-104/05 | Batch ID: R37256 | Test Code: BTXEW | Units: µg/L | Analysis Date: 10/4/05 8:29:45 PM | | | Prep Date: | | | | |
| Client ID: | | Run ID: ORGC8_051004B | | SeqNo: | 536218 | | | | | | |
| Analyte | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| MTBE | ND | 3.0 | | | | | | | | | |
| Benzene | ND | 0.50 | | | | | | | | | |
| Toluene | 0.1150 | 0.50 | | | | | | | | | J |
| Ethylbenzene | ND | 0.50 | | | | | | | | | |
| m,p-Xylene | ND | 0.50 | | | | | | | | | |
| o-Xylene | ND | 0.50 | | | | | | | | | |
| Cis-1,2-Dichloroethylene | 0.944 | 0.10 | 1.00 | 0 | 94.3% | 85 | 115 | 0 | | | |

Qualifiers: ND - Not Detected at the Reporting Limit
J - Analyte detected below quantitation limits

S - Spike Recovery outside accepted recovery limits
R - RPD outside accepted recovery limits

B - Analyte detected in the associated Method Blank

QC SUMMARY REPORT

Method Blank

CLIENT: Winzler and Kelly
Work Order: 0509542
Project: 9012220211070, Nilsen Co., Ferndale

| Sample ID: | MB 100305 | Batch ID: | R37258 | Test Code: | GASW-MS | Units: | µg/L | Analysis Date: | 10/3/05 8:28:30 AM | Prep Date: | | |
|-------------------|------------|-----------|--------|------------------|-------------|--------|----------|----------------|--------------------|------------|----------|------|
| Client ID: | | Run ID: | | ORGCMSS2_051003A | | | | SeqNo: | 536242 | | | |
| Analyte | | Result | | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | % RPD | RPDLimit | Qual |
| TPHC Gasoline | | ND | 50 | | | | | | | | | |
| Sample ID: | MB-10/4/05 | Batch ID: | R37255 | Test Code: | TPHCGW | Units: | µg/L | Analysis Date: | 10/4/05 8:29:45 PM | Prep Date: | | |
| Client ID: | | Run ID: | | ORGCG8_051004A | | | | SeqNo: | 536199 | | | |
| Analyte | | Result | | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | % RPD | RPDLimit | Qual |
| TPHC Gas (C6-C14) | | ND | 50 | | | | | | | | | |

Qualifiers:

ND - Not Detected at the Reporting Limit

J - Analyte detected below quantitation limits

S - Spike Recovery outside accepted recovery limits

B - Analyte detected in the associated Method Blank

R - RPD outside accepted recovery limits

North Coast Laboratories, Ltd.

Date: 06-Oct-05

CLIENT: Wenzler and Kelly
 Work Order: 0509542
 Project: 9012220211070, Nilsen Co., Ferndale

QC SUMMARY REPORT

Laboratory Control Spike

| Sample ID: LCS-05637 | | Batch ID: R37259 | | Test Code: 8260OXYW | | Units: µg/L | | Analysis Date: 10/3/05 5:27:00 AM | | Prep Date: | | |
|--------------------------------|--|------------------|-------|---------------------|-------------|-------------|----------|-----------------------------------|-------------|------------|----------|------|
| Client ID: | | Run ID: | | ORGCMSS2_051003B | | | | SeqNo: 536261 | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | % RPD | RPDLimit | Qual |
| Methyl tert-butyl ether (MTBE) | | 18.95 | 1.0 | 20.0 | 0 | 94.7% | 80 | 120 | 0 | 0 | 0 | |
| Tert-butyl alcohol (TBA) | | 371.7 | 10 | 400 | 0 | 92.9% | 25 | 162 | 0 | 0 | 0 | |
| Di-isopropyl ether (DIPE) | | 19.23 | 1.0 | 20.0 | 0 | 96.1% | 80 | 120 | 0 | 0 | 0 | |
| Ethyl tert-butyl ether (ETBE) | | 18.64 | 1.0 | 20.0 | 0 | 93.2% | 77 | 120 | 0 | 0 | 0 | |
| Benzene | | 20.42 | 0.50 | 20.0 | 0 | 102% | 78 | 117 | 0 | 0 | 0 | |
| Tert-amyl methyl ether (TAME) | | 17.81 | 1.0 | 20.0 | 0 | 89.1% | 64 | 136 | 0 | 0 | 0 | |
| Toluene | | 19.52 | 0.50 | 20.0 | 0 | 97.6% | 80 | 120 | 0 | 0 | 0 | |
| Ethylbenzene | | 20.34 | 0.50 | 20.0 | 0 | 102% | 80 | 120 | 0 | 0 | 0 | |
| m,p-Xylene | | 40.18 | 0.50 | 40.0 | 0 | 100% | 80 | 120 | 0 | 0 | 0 | |
| o-Xylene | | 19.82 | 0.50 | 20.0 | 0 | 99.1% | 80 | 120 | 0 | 0 | 0 | |
| 1,4-Dichlorobenzene-d4 | | 1.12 | 0.10 | 1.00 | 0 | 112% | 81 | 139 | 0 | 0 | 0 | |
| Sample ID: LCSD-05637 | | Batch ID: R37259 | | Test Code: 8260OXYW | | Units: µg/L | | Analysis Date: 10/4/05 2:29:00 AM | | Prep Date: | | |
| Client ID: | | Run ID: | | ORGCMSS2_051003B | | | | SeqNo: 536273 | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | % RPD | RPDLimit | Qual |
| Methyl tert-butyl ether (MTBE) | | 18.38 | 1.0 | 20.0 | 0 | 91.9% | 80 | 120 | 19.0 | 3.07% | 20 | |
| Tert-butyl alcohol (TBA) | | 267.8 | 10 | 400 | 0 | 67.0% | 25 | 162 | 372 | 32.5% | 20 | R |
| Di-isopropyl ether (DIPE) | | 18.44 | 1.0 | 20.0 | 0 | 92.2% | 80 | 120 | 19.2 | 4.16% | 20 | |
| Ethyl tert-butyl ether (ETBE) | | 19.15 | 1.0 | 20.0 | 0 | 95.7% | 77 | 120 | 18.6 | 2.70% | 20 | |
| Benzene | | 20.00 | 0.50 | 20.0 | 0 | 100% | 78 | 117 | 20.4 | 2.08% | 20 | |
| Tert-amyl methyl ether (TAME) | | 17.33 | 1.0 | 20.0 | 0 | 86.7% | 64 | 136 | 17.8 | 2.74% | 20 | |
| Toluene | | 19.18 | 0.50 | 20.0 | 0 | 95.9% | 80 | 120 | 19.5 | 1.76% | 20 | |
| Ethylbenzene | | 19.69 | 0.50 | 20.0 | 0 | 98.4% | 80 | 120 | 20.3 | 3.25% | 20 | |
| m,p-Xylene | | 40.05 | 0.50 | 40.0 | 0 | 100% | 80 | 120 | 40.2 | 0.318% | 20 | |
| o-Xylene | | 19.75 | 0.50 | 20.0 | 0 | 98.7% | 80 | 120 | 19.8 | 0.364% | 20 | |
| 1,4-Dichlorobenzene-d4 | | 1.08 | 0.10 | 1.00 | 0 | 108% | 81 | 139 | 1.12 | 3.76% | 20 | |

Qualifiers:

ND - Not Detected at the Reporting Limit

J - Analyte detected below quantitation limits

S - Spike Recovery outside accepted recovery limits

R - RPD outside accepted recovery limits

B - Analyte detected in the associated Method Blank

QC SUMMARY REPORT

Laboratory Control Spike

CLIENT: Wenzler and Kelly
Work Order: 0509542
Project: 9012220211070, Nilsen Co., Ferndale

QC SUMMARY REPORT

Laboratory Control Spike

CLIENT: Wenzler and Kelly
Work Order: 0509542
Project: 9012220211070, Nilsen Co., Ferndale

| Sample ID: LCS-05638 | | Batch ID: R37256 | | Test Code: BTXEW | | Units: µg/L | | Analysis Date: 10/4/05 5:33:49 PM | | Prep Date: | | |
|--------------------------|--|------------------|-------|--------------------|-------------|-------------|----------|------------------------------------|-------------|------------|----------|------|
| Client ID: | | Run ID: | | ORGC8_051004B | | | | SeqNo: 536216 | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| MTBE | | 39.95 | 3.0 | 40.0 | 0 | 99.9% | 85 | 115 | 0 | 0 | 0 | |
| Benzene | | 5.001 | 0.50 | 5.00 | 0 | 100% | 85 | 115 | 0 | 0 | 0 | |
| Toluene | | 5.125 | 0.50 | 5.00 | 0 | 102% | 85 | 115 | 0 | 0 | 0 | |
| Ethylbenzene | | 5.167 | 0.50 | 5.00 | 0 | 103% | 85 | 115 | 0 | 0 | 0 | |
| m,p-Xylene | | 10.26 | 0.50 | 10.0 | 0 | 103% | 85 | 115 | 0 | 0 | 0 | |
| o-Xylene | | 5.131 | 0.50 | 5.00 | 0 | 103% | 85 | 115 | 0 | 0 | 0 | |
| Cis-1,2-Dichloroethylene | | 1.05 | 0.10 | 1.00 | 0 | 105% | 85 | 115 | 0 | 0 | 0 | |
| Sample ID: LCSD-05638 | | Batch ID: R37256 | | Test Code: BTXEW | | Units: µg/L | | Analysis Date: 10/4/05 11:53:09 PM | | Prep Date: | | |
| Client ID: | | Run ID: | | ORGC8_051004B | | | | SeqNo: 536224 | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| MTBE | | 38.44 | 3.0 | 40.0 | 0 | 96.1% | 85 | 115 | 40.0 | 3.84% | 15 | |
| Benzene | | 4.795 | 0.50 | 5.00 | 0 | 95.9% | 85 | 115 | 5.00 | 4.21% | 15 | |
| Toluene | | 4.873 | 0.50 | 5.00 | 0 | 97.5% | 85 | 115 | 5.12 | 5.04% | 15 | |
| Ethylbenzene | | 4.922 | 0.50 | 5.00 | 0 | 98.4% | 85 | 115 | 5.17 | 4.84% | 15 | |
| m,p-Xylene | | 9.818 | 0.50 | 10.0 | 0 | 98.2% | 85 | 115 | 10.3 | 4.42% | 15 | |
| o-Xylene | | 4.923 | 0.50 | 5.00 | 0 | 98.5% | 85 | 115 | 5.13 | 4.15% | 15 | |
| Cis-1,2-Dichloroethylene | | 1.06 | 0.10 | 1.00 | 0 | 106% | 85 | 115 | 1.05 | 0.578% | 15 | |
| Sample ID: LCS-05638 | | Batch ID: R37258 | | Test Code: GASW-MS | | Units: µg/L | | Analysis Date: 10/3/05 6:58:00 AM | | Prep Date: | | |
| Client ID: | | Run ID: | | ORGCMS2_051003A | | | | SeqNo: 536240 | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| TPHC Gasoline | | 1.036 | 50 | 1,000 | 0 | 104% | 80 | 120 | 0 | 0 | 0 | |

Qualifiers: ND - Not Detected at the Reporting Limit
J - Analyte detected below quantitation limits

S - Spike Recovery outside accepted recovery limits
R - RPD outside accepted recovery limits

B - Analyte detected in the associated Method Blank

CLIENT: Winzler and Kelly
Work Order: 0509542
Project: 9012220211070, Nilsen Co., Ferndale

QC SUMMARY REPORT


Laboratory Control Spike Duplicate

| Sample ID: | LCSD-05638 | Batch ID: | R37258 | Test Code: | GASW/MS | Units: | µg/L | Analysis Date: | 10/4/05 2:58:00 AM | Prep Date: | | |
|-------------------|------------|-----------|-----------------|------------|-------------|--------|----------|----------------|---------------------|------------|----------|------|
| Client ID: | | Run ID: | ORGCMS2_051003A | SeqNo: | 536252 | | | | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| TPHC Gasoline | | 1,037 | 50 | 1,000 | 0 | 104% | 80 | 120 | 1,040 | 0.145% | 20 | |
| Sample ID: | LCs-05639 | Batch ID: | R37255 | Test Code: | TPHCGW | Units: | µg/L | Analysis Date: | 10/4/05 6:44:26 PM | Prep Date: | | |
| Client ID: | | Run ID: | ORGCS_051004A | SeqNo: | 536197 | | | | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| TPHC Gas (C6-C14) | | 482.4 | 50 | 500 | 0 | 96.5% | 85 | 115 | 0 | 0 | | |
| Sample ID: | LCSD-05638 | Batch ID: | R37255 | Test Code: | TPHCGW | Units: | µg/L | Analysis Date: | 10/5/05 12:32:44 AM | Prep Date: | | |
| Client ID: | | Run ID: | ORGCS_051004A | SeqNo: | 536205 | | | | | | | |
| Analyte | | Result | Limit | SPK value | SPK Ref Val | % Rec | LowLimit | HighLimit | RPD Ref Val | %RPD | RPDLimit | Qual |
| TPHC Gas (C6-C14) | | 483.5 | 50 | 500 | 0 | 96.7% | 85 | 115 | 482 | 0.231% | 15 | |

Qualifiers: ND - Not Detected at the Reporting Limit
J - Analyte detected below quantitation limits

S - Spike Recovery outside accepted recovery limits
R - RPD outside accepted recovery limits

B - Analyte detected in the associated Method Blank



**NORTH COAST
LABORATORIES LTD.**

5580 West End Road • Arcata • CA 95521-9202
707-822-4649 Fax 707-822-6831

Chain of Custody

55680 West End Road • Arcata • CA 95521-9202
707-822-4649 Fax 707-822-6831

LABORATORY NUMBER:

Part 1: Knowledge

卷之三

to: John Galt in Book 1

Digitized by sscsi

卷之三

卷之三

Print): Green

PROJECT INFORMATION
000330211930

Wiltshire Co., England

Number: _____

| SAMPLE ID | DATE | TIME | MAT |
|-----------|----------|-------|-----|
| 1-5 | 01/23/06 | 11:20 | 6 |

A decorative floral border at the top of the page, featuring stylized leaves and flowers in a repeating pattern.

卷之三

1795
1796

卷之三

卷之三

CHIEFD BY (Sign & Print) DATE/TIME

17315

卷之三

| Attention: | | Results & Invoice to: | | Address: | | CONTAINER PRESERVATIVE | | ANALYSIS | | DATE/TIME | |
|--------------------------------|-----------|-----------------------|------|-------------------------------|---|------------------------|---|---------------------------|---|--------------|---|
| Pat Kasprowi | | Winfred L. Cole | | 625 3rd St Aurea, CA 95501 | | Safeguard | | 90926 | | 4-23-05 1300 | |
| Phone: | | Copies of Report to: | | | | | | | | | |
| | | | | | | | | | | | |
| PROJECT INFORMATION | | | | | | | | | | | |
| Project Number: | | 401220211020 | | Project Name: | | Wilson Co, Fendrille | | | | | |
| Purchase Order Number: | | | | | | | | | | | |
| LAB ID | SAMPLE ID | DATE | TIME | MATRIX* | | | | | | | |
| MW - 5 | 4/23/05 | 1120 | AM | X | X | X | X | X | X | X | X |
| MW - 10 | | 1125 | | X | X | X | X | X | X | X | X |
| MW - 2 | | 1130 | | X | X | X | X | X | X | X | X |
| MW - 3 | | 1205 | | X | X | X | X | X | X | X | X |
| MW - 8 | | 1211 | | X | X | X | X | X | X | X | X |
| MW - 16 | | 1222 | | X | X | X | X | X | X | X | X |
| MW - 1 | | 1230 | | X | X | X | X | X | X | X | X |
| Data Manager To: Pat Kasprowi | | Initials: PK | | Date: 4-23-05 | | Initials: PK | | Date: 4-23-05 | | Initials: PK | |
| RECEIVED BY (Sign) | | | | | | | | | | | |
| RELINQUISHED BY (Sign & Print) | | DATE/TIME | | RECEIVED BY (Sign) | | DATE/TIME | | RECEIVED BY (Sign) | | DATE/TIME | |
| Gary S. Foster Gary S. Foster | | 4/23/05 1300 | | John S. Mays John S. Mays | | 4/23/05 1300 | | John S. Mays John S. Mays | | 4/23/05 1300 | |

MATRIX: DW=Drinking Water; Eff=Effluent; Inf=Influent; SW=Surface Water; GW=Ground Water; S=Soil; O=Other.

ALL CONTAMINATED NON-AQUEOUS SAMPLES WILL BE RETURNED TO CLIENT

Appendix D

Standard Operating Procedures

WINZLER & KELLY CONSULTING ENGINEERS

STANDARD OPERATING PROCEDURES GROUNDWATER LEVEL MEASUREMENTS AND FREE PHASE HYDROCARBON MEASUREMENTS

1. Objective

To establish accepted procedures for detecting free-phase hydrocarbons and measuring groundwater levels in monitoring wells.

2. Background

Any time water levels are required to determine the groundwater flow gradient or flow direction, water levels are collected. Wells are tested for free-phase hydrocarbons prior to insertion of electronic water level probes or purge pumps the first time a well is sampled and in any well that has a history of free-phase hydrocarbons.

3. Personnel Required and Responsibilities

Project Manager: The Project Manager (PM) is responsible for ensuring that field personnel have been trained in these procedures and for verifying that water levels have been collected in compliance with this SOP.

Field Technician: The Field Technician is responsible for complying with this SOP, including determining if there are free phase hydrocarbons in the well, the thickness (if it exists) and the stabilized water level in the well.

4. Equipment Required

- Water level/free phase hydrocarbon indicator probe or pastes
- Tape measure
- Water Level Data Form/pencil
- Watch
- Disposable gloves
- Distilled water
- Alconox soap
- Containers to hold rinsate water
- Site Safety Plan and Hospital Map
- Keys to wells
- Tools to open wells

5. Procedure

After reviewing the Site Safety Plan and determining the type and concentrations of contaminants that may be present on site, the field personnel will don the proper level of personal protection prior to opening any wells.

Open all monitoring wells to be measured and remove expandable caps. Allow wells to equilibrate 5 to 15 minutes. Record time and visual observations regarding well access, condition, security, etc on water level data sheet.

5a. Alternative procedure for electronic water-level/free-phase hydrocarbon indicator

- Decontaminate probe with potable water and Alconox mix. Rinse with distilled water.
- Lower probe into the well and determine the presence of any free-phase hydrocarbons. The probe will emit a continuous sound if free product is present. If no product is present, the probe will make an oscillating (beeping) sound when it encounters water. Record the depth of free-phase hydrocarbons on the water level data sheet. If no free-phase hydrocarbons are present, record the water depth. **DO NOT SUBMERGE THE PROBE THROUGH THE FLOATING PRODUCT LAYER.**
- Gradient calculations shall then be performed by calculation of the groundwater elevation by:
 - GW ELEV = (TOC) - (depth to water).
 - TOC indicates top of casing elevation as surveyed.
 - If free-phase hydrocarbons are indicated, determine the depth to water using a steel measuring tape and water indicator paste, by the procedure below.

5b. Alternative procedure for product and water indicator pastes

- Decontaminate tape measure.
- Place **product** indicator paste on bottom two feet of tape measure.
- Lower tape measure into well. Note depth to which the end of the tape is lowered relative to the point of survey mark on the top of the well casing.
- Withdraw the tape. If paste has changed color, free-phase hydrocarbons are present. Calculate depth to the floating layer by:
 - Depth to Product = (depth to which tape lowered into well) - (length of product indicator paste discoloration).
- Remove product indicator paste with paper towel and decontaminate tape measure.
- Apply **water** indicator paste on bottom two feet of tape measure.
- Lower tape into well. Note depth to which end of tape is lowered.
- Withdraw the tape. Calculate the depth to water by:
 - Depth to Water = (depth to which tape lowered into well) - (length of water indicator paste discoloration).
- Obtain the depth to groundwater level readings from the point of survey mark, or from the North side of the top of the casing, if no point of survey mark is present. Readings will be measured to the nearest 0.01 foot. Note time and readings on water level data sheet.
- Use the same measuring device to measure water levels in all wells to be used in the gradient calculation.

- Obtain depth to casing bottom for each well by submerging a tape measure until it reaches the bottom of the well. Readings will be measured to the nearest 0.01 foot. Note readings on data sheet. If sampling is not going to be completed at the site, close and lock all wells.
- Gradient calculations shall then be conducted by making water depth corrections for the presence of free product. First calculate the product thickness:
 - Product Thickness = (Depth to Water) - (Depth to Product).
 - Water elevations when free product is present shall then be calculated by:
 - $GW\ ELEV = (TOC) - (Depth\ to\ Water) - SG_{product}\ (Product\ Thickness)$
 - On any site where monitoring will occur more than once, a free product sample will be collected and measured for specific gravity ($SG_{product}$). In the absence of the site specific free product specific gravity $SG_{product}$ shall be assumed to be 0.78.

WINZLER & KELLY CONSULTING ENGINEERS

STANDARD OPERATING PROCEDURES for MONITORING WELL PURGING AND SAMPLING ACTIVITIES

1.0 OBJECTIVE

To establish accepted procedures for the purging and sampling groundwater from monitoring wells, to ensure that representative samples of formation water are collected by accepted methods.

1.1 Background

To obtain a representative groundwater sample from monitor wells, it is necessary to remove (purge) stagnant water from within and near the well prior to sampling. In general, three to seven casing volumes must be removed from the well prior to sampling, to provide a representative sample. Wells may be sampled after purging less than the minimum three volumes if well recharge rates are beyond reasonable time constraints. The specific method of well purging will be decided on a case by case basis, or as required by project specifications.

1.2 Personnel Required and Responsibilities

Project Manager: The Project Manager (PM) is responsible for ensuring that field personnel have been trained in the use of these procedures and for verifying that monitoring well purging and sampling activities are performed in compliance with these SOP's.

Field Technician: The Field Technician is responsible for complying with these SOP's, including the purging and sampling of monitor wells, the safe containerization of extracted waters, the documentation of field procedures, and the handling of samples..

2.0 WELL PURGING ACTIVITIES

2.1 Equipment Required

- Bottom-filling bailer, suction air pump, air-lift pump, gas operated (bladder) pump, submersible pump, or other pumping device
- pH meter
- Conductivity/Temperature Meter
- Water Level Indicator
- Well Sampling Data Sheet
- Indelible marker
- Disposable gloves
- Containers to hold extracted water (as required)

2.2. Purging Procedure

Prior to groundwater sampling, each monitoring well will be purged as described below. Prior to insertion into each well, all equipment will be either decontaminated (following W&K Decontamination procedures) or will be deemed clean or previously unused by the manufacturer.

- Open all monitoring wells to be purged and allow to equilibrate 5 to 15 minutes. Record time and visual observations regarding well access, condition, security, etc. in log book.
- Obtain depth to groundwater level readings according to Winzler & Kelly Standard Operating Procedures for Groundwater Level measurements and Free Phase Hydrocarbon Measurements. Record time and readings on the Well Level Measurement Data Sheet.
- Calculate the volume of standing water in each monitoring well. Record the volume calculated for each well on the Well Sampling Data Sheet.
- Begin purging the well by removing water from the well and collecting in a calibrated container (i.e., 5-gallon bucket marked in 1-gallon increments). The depth, or interval, from which the water is being purged should be noted on the data sheet.
- Obtain readings of field parameters (pH, conductivity, temperature, and turbidity) and make visual observations of color/odor/turbidity at selected intervals (i.e., every gallon, every five gallons, etc.) throughout the purging process. Depending on the calculated volume and the expected number of gallons to be purged, a minimum of five readings should be collected. Record the time, readings, and visual comments on the Purge Data Sheet.
- Continue purging until at least three (minimum) to four well volumes have been removed and the field parameters stabilize to within:

| | |
|--------------|------|
| pH | ~0.1 |
| conductivity | ~10% |
| turbidity | ~10% |
| temperature | ~1° |

- Do not exceed seven well volumes.
- Obtain a final depth to groundwater level measurement prior to collection of the groundwater sample and note the reading and time on the Well Level Measurement Data Sheet. Be sure that the measurement probe has been thoroughly decontaminated prior to insertion into each well. Note any qualitative comments regarding recharge rate of each well, and calculate the percent of the original water column that has recovered at the time of the final depth measurement. It is ideal to attain a minimum of 80% water level recovery prior to sampling, if time constraints allow. Very slow recharge rates may not allow purging the minimum three volumes or 80% recovery; lesser volumes may be used for sampling, as needed and documented.
 - Collect a groundwater sample following the directions below under Section 3.0.

- Containerize all purge water and decontamination water in 55-gallon drums. Use yellow indelible markers (storeroom supply) to label all drums on the side with date, contents, origin and other pertinent information. Avoid marking the tops of drums with black marker, such marks are temporary and will soon fade/rust. Note the number, condition and location of drums on site in the field notes.

3.0 WELL SAMPLING ACTIVITIES

3.1 Equipment Required

- Disposable bailer (previously unused) *
- Bottom emptying device (sampling port)
- Monofilament nylon line (min 40-lb test)
- Monitor Well Purge & Sample Data Sheets
- Sample containers (preserved, as required) - provided by the laboratory
- Sample labels
- Indelible marker
- Disposal gloves
- Decontamination soap (Alconox)
- Distilled water for equipment decontamination.

*A variety of sampling techniques are available for the collection of groundwater samples. Except where otherwise required, W&K only utilizes disposable polyethylene bailers to collect groundwater samples.

3.2 Sampling Procedure

Prior to collecting a groundwater sample from a monitoring well, each well must be properly purged in accordance with W&K's SOP for Monitoring Well Purging Activities (See Section 2.0 above), including the measurement of the final water level and documentation of recharge.

- Water from the desired screen interval will be collected by lowering the previously unused disposable, polyethylene, bottom-filling bailer into the well.
- When bailer is completely full, carefully retract the bailer from the well casing.
- Using a previously unused, new, bottom-emptying device, to minimize agitation of the water, transfer the water from the bailer to the sample containers.
- When sampling for volatile constituents (VOA's), the water samples will be collected in 40-ml glass vials (preserved as required by the analyses requested). Precautions will be taken to prevent capturing air bubbles in the vials.
- Upon filling, each vial will be immediately capped with a Teflon septum and plastic screw cap. The vial will be checked for air bubbles by inverting and gently tapping the vial. If any bubbles are visible, the vial will be refilled and confirmed to be free of any air bubbles.

- At a minimum, all samples will be labeled with the following information:

| | |
|----------------|--------------------------------|
| Sample ID | Date and Time Sample Collected |
| Location | Sampler's Initials |
| Project Number | Analyses Requested |
- Sample information will be documented on the Chain-of-Custody form. All samples will be placed in an ice chest, chilled to a temperature of 4°C. The ice chest will remain in the custody of the sampler until it is transferred to the courier service for delivery at the analytical laboratory for analyses. Any and all transfer of sample custody must be documented on the Chain-of-Custody form with the name, signature, affiliation, date and time of the persons releasing and receiving custody of the samples.
- Upon completion of the sampling activities, each well shall be closed and secured by replacing the well cap and securing the lock.
- Dispose of gloves, bailers, bottom-emptying devices, and bailing line after each use.

Appendix E

Field Notes

WELL SAMPLING DATA SHEET

PROJECT NAME: Nilsen
 PROJECT NUMBER: 90122202 1172
 WELL DESIGNATION: MW - 1

PROJECT DATE: 9/22/05
 SAMPLER: Lester
 SAMPLE NUMBER: MW - 1

CONDITION OF WELL HEAD/VULT/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
- B. DEPTH TO GROUNDWATER (initial): 4.07
- C. DEPTH OF WELL: MEASURED 11.42
- D. HEIGHT OF WATER COLUMN (C-B): 7.35
- E. GROUNDWATER ELEVATION (A-B): 7.35

CASING DIAMETER: 2" 3" 4" OTHER _____

CALCULATED WELL VOLUME: D X V = 7.35 · 653 = 4.8 = 14.5 ...
 Volume (V) of 2" well - 0.163 gal/ft
 Volume (V) of 4" well - 0.653 gal/ft

ODOR SHEEN

FLOATING PRODUCT THICKNESS _____

PUMP TYPE: POLY BAILER _____
 ELECTRIC _____

STAINLESS BAILER _____
 OTHER _____

PUMP DEPTH:

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mmhos/cm or μmhos/cm) | TURBIDITY (NTU or visual) |
|------|----------------|---------------------|------|------------------------|-------------------------------------|---------------------------|
| 0920 | initial | — | 6.46 | 20.2 | 731 | yellowish |
| 0935 | 5.0 | | 6.41 | 20.1 | 805 | murky |
| 0945 | 10.0 | | 6.74 | 19.7 | 824 | " |
| 0955 | 12.5 | | 6.56 | 18.9 | 809 | " |
| 1000 | 13.5 | | 6.60 | 18.7 | 801 | 1+ |
| 1010 | 14.0 | | 6.69 | 18.5 | 807 | " |
| 1025 | 14.5 | | 6.71 | 18.9 | 795 | 0 |

RECHARGE RATE (qualitative): slow

SAMPLER TYPE: TEFILON BAILER _____

ACRYLIC BAILER _____

DISPOSABLE BAILER

SAMPLES COLLECTED: PRESERVED VOA'S 3 UNPRESERVED VOA'S _____
 PRESERVED LITERS _____ UNPRESERVED LITERS _____
 500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
 FILTERED _____ UNFILTERED _____
 OTHER _____

COMMENTS:

$\Delta D = 0.6$

Sample

0 12.2.2

WELL SAMPLING DATA SHEET

PROJECT NAME: Milsey
 PROJECT NUMBER: 90122202 11072
 WELL DESIGNATION: MW-2

PROJECT DATE: 9/23/05
 SAMPLER: Lester
 SAMPLE NUMBER: MW-2

CONDITION OF WELL HEAD/VULT/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
 B. DEPTH TO GROUNDWATER (initial): 3.74
 C. DEPTH OF WELL:
 D. HEIGHT OF WATER COLUMN (C-B): 6.71 MEASURED 10.45
 E. GROUNDWATER ELEVATION (A-B):

CASING DIAMETER: 2" 3" 4" OTHER

CALCULATED WELL VOLUME: D X V = 6.71 . 163 = (1.5 . 3 . 3.3) ...
 Volume (V) of 2" well - 0.163 gal/m
 Volume (V) of 4" well - 0.653 gal/m

ODOR _____ SHEEN _____ FLOWING PRODUCT THICKNESS _____
 PUMP TYPE: POLY BAILEY _____ STAINLESS BAILEY _____
 ELECTRIC _____ OTHER _____

PUMP DEPTH:

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mmhos/cm or μmhos/cm) | TURBIDITY (NTU or visual) |
|------|----------------|---------------------|------|------------------------|-------------------------------------|---------------------------|
| 0.08 | Initial | ~ | 6.46 | 20.0 | 271 | clear |
| 1.0 | | | 6.74 | 18.6 | 278 | cloudy |
| 1.75 | | | 6.81 | 18.4 | 275 | cloudy |
| 2.5 | | | 6.83 | 17.9 | 269 | cloudy |
| 2.75 | | | 6.84 | 17.8 | 259 | cloudy |
| 3.0 | | | 6.86 | 17.8 | 258 | " |
| 3.5 | | | 6.87 | 17.7 | 257 | " |

RECHARGE RATE (qualitative): Good

SAMPLER TYPE: TEFLO N BAILEY _____ ACRYLIC BAILEY _____ DISPOSABLE BAILEY

SAMPLES COLLECTED: PRESERVED VOA'S _____ UNPRESERVED VOA'S _____
 PRESERVED LITERS _____ UNPRESERVED LITERS _____
 500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
 FILTERED _____ UNFILTERED _____
 OTHER _____

COMMENTS:

Sample
 1139
 DD 1.4.

WELL SAMPLING DATA SHEET

PROJECT NAME: Wilson
 PROJECT NUMBER: 90122202 11072
 WELL DESIGNATION: MW-3

PROJECT DATE: 9/23/03
 SAMPLER: Lester
 SAMPLE NUMBER: MW-3

CONDITION OF WELL HEAD/VAUTL/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
 B. DEPTH TO GROUNDWATER (initial): 4.56
 C. DEPTH OF WELL: MEASURED 9.95
 D. HEIGHT OF WATER COLUMN (C-B):
 E. GROUNDWATER ELEVATION (A-B): 5.39

CASING DIAMETER: 2" ✓ 3" 4" OTHER _____

CALCULATED WELL VOLUME: D X V = 5.39 · 163 = 873 ...
 Volume (V) of 2" well - 0.163 gal/ft
 Volume (V) of 4" well - 0.653 gal/ft

ODOR No SHEEN No FLOATING PRODUCT THICKNESS _____

PUMP TYPE: POLY BAILER _____ STAINLESS BAILER _____
 ELECTRIC _____ OTHER _____

PUMP DEPTH:

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mmhos/cm or μ mhos/cm) | TURBIDITY (NTU or visual) |
|------|----------------|---------------------|------|------------------------|--|---------------------------|
| 236 | Initial | - | 6.44 | 19.0 | 274 | clear |
| 247 | 2.5 | | 6.81 | 19.3 | 325 | frothy |
| 251 | 2.0 | | 6.94 | 19.3 | 323 | frothy |
| 255 | 2.5 | | 7.04 | 18.9 | 331 | 11 |
| 300 | 3.0 | | 7.08 | 19.0 | 330 | 11 |
| | | | | | | |
| | | | | | | |

RECHARGE RATE (qualitative): Good

SAMPLER TYPE: TEFLO N BAILER _____ ACRYLIC BAILER _____ DISPOSABLE BAILER ✓

SAMPLES COLLECTED: PRESERVED VOA'S 3 UNPRESERVED VOA'S _____
 PRESERVED LITERS _____ UNPRESERVED LITERS _____
 500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
 FILTERED _____ UNFILTERED _____
 OTHER _____

COMMENTS:

$D_s = 6.0$

Sample

1150

PROJECT NAME: Nilsen
PROJECT NUMBER: 10122202 W072
WELL DESIGNATION: MW-5PROJECT DATE: 7/22/05
SAMPLER: Lester
SAMPLE NUMBER: MW-5

CONDITION OF WELL HEAD/VAULT/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
 B. DEPTH TO GROUNDWATER (initial): 5.02
 C. DEPTH OF WELL: MEASURED 12.25
 D. HEIGHT OF WATER COLUMN (C-B): 7.23
 E. GROUNDWATER ELEVATION (A-B):

CASING DIAMETER: 2" 3" 4" OTHER CALCULATED WELL VOLUME: D X V = 7.23 · 1.63 = 12.3 · 3 = 3.55 ...
 Volume (V) of 2" well - 0.163 gal/m
 Volume (V) of 4" well - 0.653 gal/mODOR noSHEEN no

FLOATING PRODUCT THICKNESS _____

PUMP TYPE: POLY BAILER
ELECTRIC STAINLESS BAILER
OTHER

PUMP DEPTH:

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mmhos/cm or μmhos/cm) | TURBIDITY (NTU or visual) |
|------|----------------|---------------------|------|------------------------|-------------------------------------|---------------------------|
| 1230 | initial | — | 4.89 | 17.2 | 391 μs/cm | clear |
| 1245 | 2.0 | 1.4 | 5.01 | 17.0 | 690 μs/cm | v. turbid |
| 1250 | 2.5 | 2.1 | 5.21 | 15.3 | 728 μs/cm | v turbid |
| 1255 | 3.0 | 2.7 | 5.24 | 15.2 | 731 μs/cm | " " |
| 1300 | 3.5 | 3.0 | 5.27 | 15.6 | 710 μs/cm | " " |
| | , | , | , | , | , | |
| | , | , | , | , | , | |

RECHARGE RATE (qualitative): appear goodSAMPLER TYPE: TEFLON BAILER ACRYLIC BAILER DISPOSABLE BAILER SAMPLES COLLECTED: PRESERVED VOA'S 3 UNPRESERVED VOA'S
PRESERVED LITERS UNPRESERVED LITERS
500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
FILTERED UNFILTERED
OTHER

COMMENTS:

D_o = 5.0sampled H2O4 baile ① 2.5
never dry

WELL SAMPLING DATA SHEET

PROJECT NAME: Nilsen
PROJECT NUMBER: 901022202 11072
WELL DESIGNATION: MW-6PROJECT DATE: 9/23/05
SAMPLER: Lester
SAMPLE NUMBER: MW-6

CONDITION OF WELL HEAD/VAULT/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
 B. DEPTH TO GROUNDWATER (initial): 4.59
 C. DEPTH OF WELL: MEASURED 9.75
 D. HEIGHT OF WATER COLUMN (C-B):
 E. GROUNDWATER ELEVATION (A-B): 5.16

CASING DIAMETER: 2" 3" 4" OTHER _____CALCULATED WELL VOLUME: D X V = 5.16 163 \pm .84 = 2.5 gallons
 Volume (V) of 2" well - 0.163 gal/ft
 Volume (V) of 4" well - 0.653 gal/ftODOR yes SHEEN no FLOATING PRODUCT THICKNESS _____PUMP TYPE: POLY BAILER _____ STAINLESS BAILER _____
 ELECTRIC _____ OTHER _____

PUMP DEPTH:

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mmhos/cm or μ mhos/cm) | TURBIDITY (NTU or visual) |
|------|----------------|---------------------|------|------------------------|--|---------------------------|
| 0830 | Initial | - | 6.07 | 22.5 | 473 | clear |
| 0840 | 1.5 | 1.9 | 6.42 | 21.1 | 541 | turbid |
| 0850 | 2.0 | 2.4 | 6.28 | 20.8 | 539 | cloudy |
| 0855 | 2.25 | 2.7 | 6.25 | 20.6 | 544 | cloudy |
| 0900 | 2.50 | 3.0 | 6.26 | 20.4 | 542 | |
| | , | | | | | |
| | , | | | | | |

RECHARGE RATE (qualitative): goodSAMPLER TYPE: TEFLO N BAILER _____ ACRYLIC BAILER _____ DISPOSABLE BAILER SAMPLES COLLECTED: PRESERVED VOA'S 3 UNPRESERVED VOA'S _____
 PRESERVED LITERS _____ UNPRESERVED LITERS _____
 500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
 FILTERED _____ UNFILTERED _____
 OTHER _____

COMMENTS:

DO = 0.8 mg/lSample 1211

PROJECT NAME: Misen
PROJECT NUMBER: 90122202 11072
WELL DESIGNATION: MW-8PROJECT DATE: 9/23/85
SAMPLER: Carter
SAMPLE NUMBER: MW-8

CONDITION OF WELL HEAD/VULT/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
 B. DEPTH TO GROUNDWATER (initial): 3.98
 C. DEPTH OF WELL: MEASURED (4.88)
 D. HEIGHT OF WATER COLUMN (C-B):
 E. GROUNDWATER ELEVATION (A-B): 0.90

CASING DIAMETER: 2" 3" 4" OTHER _____CALCULATED WELL VOLUME: $D \times V = 10.40 \cdot 163 = 1.8 \cdot 3 = 5.4$...
 Volume (V) of 2" well - 0.163 gal/ft
 Volume (V) of 4" well - 0.653 gal/ftODOR N/A SHEEN No FLOATING PRODUCT THICKNESS _____PUMP TYPE: POLY BAILER _____ STAINLESS BAILER _____
 ELECTRIC _____ OTHER _____

PUMP DEPTH: _____

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mmhos/cm or μ mhos/cm) | TURBIDITY (NTU or visual) |
|------|----------------|---------------------|------|------------------------|--|---------------------------|
| 3:0 | initial | — | 6.57 | 19.3 | 705 | clear |
| 3:20 | 2.0 | 1.1 | 6.74 | 21.3 | 721 | turbid |
| 3:30 | 3.5 | 1.9 | 6.83 | 21.2 | 740 | " |
| 3:40 | 4.5 | 2.2 | 7.01 | 21.0 | 728 | " |
| 3:45 | 5.0 | 2.8 | 7.04 | 20.7 | 721 | " |
| 3:50 | 5.5 | 3.1 | 7.06 | 20.6 | 723 | " |
| 4:00 | 6.0 | 3.5 | 7.05 | 20.8 | 719 | " |

RECHARGE RATE (qualitative): goodSAMPLER TYPE: TEFLO N BAILER _____ ACRYLIC BAILER _____ DISPOSABLE BAILER SAMPLES COLLECTED: PRESERVED VOA'S 3 UNPRESERVED VOA'S _____
 PRESERVED LITERS _____ UNPRESERVED LITERS _____
 500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
 FILTERED _____ UNFILTERED _____
 OTHER _____

COMMENTS:

 $D_0 = 0.4 \text{ mg/L}$

Sample 1205

WELL SAMPLING DATA SHEET

PROJECT NAME: Nilsen
 PROJECT NUMBER: 901220-02 11072
 WELL DESIGNATION: MW-9

PROJECT DATE: 9/22/05
 SAMPLER: Lester
 SAMPLE NUMBER: MW-9

CONDITION OF WELL HEAD/VULT/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
- B. DEPTH TO GROUNDWATER (initial): 3.98
- C. DEPTH OF WELL: 10.89 MEASURED 14.87
- D. HEIGHT OF WATER COLUMN (C-B): 10.89
- E. GROUNDWATER ELEVATION (A-B):

CASING DIAMETER: 2" 3" 4" OTHER

CALCULATED WELL VOLUME: D X V = (0.89 \cdot 163 = 1.8 \approx 5.4)
 Volume (V) of 2" well - 0.163 gal/ft
 Volume (V) of 4" well - 0.653 gal/ft

ODOR _____ SHEEN _____ FLOWING PRODUCT THICKNESS _____
 PUMP TYPE: POLY BAILER _____ STAINLESS BAILER _____
 ELECTRIC _____ OTHER _____

PUMP DEPTH:

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mhos/cm or μ mhos/cm) | TURBIDITY (NTU OR visual) |
|------|----------------|---------------------|------|------------------------|---|---------------------------|
| 1180 | initial | — | 5.39 | 10.3 | 590 μ s/cm | clear |
| 1200 | 2.0 | 1.1 | 5.29 | 18.4 | 771 μ s/cm | sl. cloudy |
| 1205 | 3.5 | 1.9 | 5.27 | 17.8 | 842 μ s/cm | " " |
| 1207 | 4.0 | 2.3 | 5.26 | 17.6 | 911 μ s/cm | turbid |
| 1212 | 4.5 | 2.7 | 5.16 | 17.4 | 907 μ s/cm | turbid |
| 1217 | 5.0 | | | | | |
| 1217 | 5.5 | | | | | |

RECHARGE RATE (qualitative):

SAMPLER TYPE: TEFILON BAILER _____ ACRYLIC BAILER _____ DISPOSABLE BAILER

SAMPLES COLLECTED: PRESERVED VOA'S 3 UNPRESERVED VOA'S _____
 PRESERVED LITERS _____ UNPRESERVED LITERS _____
 500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
 FILTERED _____ UNFILTERED _____
 OTHER _____

COMMENTS:

DD 1.0 m) 1
 1/2 barrels Ø 3.55
 1/4 barrels Ø 4.0
 dry Ø 4.5
 1/2 30
 1/2 30
 1/2 30
 1/2 30

WELL SAMPLING DATA SHEET

PROJECT NAME: Nilson
 PROJECT NUMBER: 90122202 11072
 WELL DESIGNATION: MW-10

PROJECT DATE: 9/22/05
 SAMPLER: Lester
 SAMPLE NUMBER: MW-10

CONDITION OF WELL HEAD/VULT/CAP & LOCK:

- A. TOP OF CASING ELEVATION:
- B. DEPTH TO GROUNDWATER (initial): 3.28
- C. DEPTH OF WELL: MEASURED 14.87
- D. HEIGHT OF WATER COLUMN (C-B): 11.59
- E. GROUNDWATER ELEVATION (A-B):

CASING DIAMETER: 2" 3" 4" OTHER

CALCULATED WELL VOLUME: D X V = $11.59 \cdot 163 = 23 \cdot 3 = 6$
 Volume (V) of 2" well - 0.163 gal/ft
 Volume (V) of 4" well - 0.653 gal/ft

ODOR noSHEEN NoFLOATING PRODUCT THICKNESS

PUMP TYPE: POLY BAILER
 ELECTRIC

STAINLESS BAILER
 OTHER

PUMP DEPTH:

| TIME | GALLONS PURGED | NO. OF WELL VOLUMES | pH | TEMPERATURE (°F OR °C) | CONDUCTIVITY (mmhos/cm or µmhos/cm) | TURBIDITY (NTU or visual) |
|------|----------------|---------------------|------|------------------------|-------------------------------------|---------------------------|
| 1315 | initial | — | 5.09 | 20.4 | 482 | |
| 1335 | 2.0 | 1 | 5.66 | 20.9 | 485 | clear |
| 1345 | 3.5 | 1.5 | 5.69 | 20.8 | 501 | cloudy |
| 1350 | 4.5 | 2.2 | 5.56 | 21.0 | 498 | turbid |
| 1355 | 5.5 | 2.5 | 5.64 | 20.0 | 489 | ++ |
| 1359 | 6.0 | 3.0 | 5.77 | 19.6 | 491 | ++ |

RECHARGE RATE (qualitative): GoodSAMPLER TYPE: TEFLO N BAILER ACRYLIC BAILER DISPOSABLE BAILER

SAMPLES COLLECTED:

PRESERVED VOA'S 3 UNPRESERVED VOA'S
 PRESERVED LITERS UNPRESERVED LITERS
 500 ml PLASTIC BOTTLE WITH PRESERVATIVE FOR METALS:
 FILTERED UNFILTERED
 OTHER

COMMENTS:

DO : 3.0Sample
1125



By GSC Date 9/22/05 Client Nielsen
Subject Y4 Sampling Sheet No. _____ of _____
Job No. 90122208.11070

Thursday Sept. 22, 2005

0800 pack up field supplies / sample items

0830 pickup DOT drum from Renner

0900 Arrive at site

0900-1040 open wells

1100-1135 water levels

1140-1200 purge wells

1200-1230 secure site / visit barn for drum inventory

was told by barn staff that the drum storage was becoming burdensome. They refused to store an empty drum overnight for me.

Friday Sept. 23, 2005

830 Arrive at site

900-1030 purge wells MW-1, 6

11-1:00pm sample wells

1:10-2:30 prepare samples for lab / secure site

3:00 Return unsealed DOT drum to Renner

3-4:00 Prepare notes / assist lab pick up of samples

CONSULTING ENGINEERS WATER LEVEL MEASUREMENT DATA SHEET

PROJECT NAME: Nilsen
PROJECT NUMBER: 90122202.11057

TODAY'S DATE: 9/22/05
FIELD PERSONNEL: Lester

DISSOLVED OXYGEN MEASUREMENT FORM

PROJECT NAME: Nilsen
PROJECT NUMBER: 90122203 1107

TODAY'S DATE: 9/23-24/05
FIELD PERSONNEL: Lester